BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of Work: Maintenance and Development of Park in Ward No. 09, Vidyaranyapura.

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
1	121.05	Excavation for road, drains and similar works KSRRB 300-1. Earthwork **excavation by manual means in ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	199.36	Rupees One Hundred Ninety Nine And Paise Thirty Six Only
2	25.54	Providing and laying in position **plain cement concrete of mix 1:3:6** with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation** including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5348.76	Rupees Five Thousand Three Hundred Forty Eight And Paise Seventy Six Only
3	38.21	Providing and laying **cement concrete** using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Ready mixed Cement concrete for Beams, Staircase and Roof with M-25** etc complete as per specifications and directions of engineer in charge of the work	Cum	6428.90	Rupees Six Thousand Four Hundred Twenty Eight And Paise Ninety Only
	35.79	Qty Above 125%		5770.64	Rupees Five Thousand Seven Hundred Seventy And Paise Sixty Four Only
4	4.59	Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - **TMT bars Fe 500** etc complete as per specifications and directions of engineer in charge of the work	Tonne	64243.42	Rupees Sixty Four Thousand Two Hundred Forty Three And Paise Forty Two Only
	3.92	Qty Above 125%		75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three And Paise Ninety Six Only

EXECUTIVE ENGINEER-4
KRIDE BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
5	210.80	Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for **vertical surface such as walls at any thickness**, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	310.58	Rupees Three Hundred Ten And Paise Fifty Eight Only
	74.20	Qty Above 125%		379.48	Rupees Three Hundred Seventy Nine And Paise Forty Eight Only
6	29.40	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6, stone** hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4438.22	Rupees Four Thousand Four Hundred Thirty Eight And Paise Twenty Two Only
7	22.05	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5305.30	Rupees Five Thousand Three Hundred Five And Paise Thirty Only
8	180.00	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	103.88	Rupees One Hundred Three And Paise Eighty Eight Only
9	9.00	Providing and laying in position **plain cement concrete of mix 1:2:4** with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation, plinth and cills**, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven And Paise Forty Six Only
	4.00	Qty Above 125%		5747.32	Rupees Five Thousand Seven Hundred Forty Seven And Paise Thirty Two Only
10	141.75	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6 mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25 cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineerin - charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete) etc complete as per specifications and directions of engineer in charge of the work	m	868.14	Rupees Eight Hundred Sixty Eight And Paise Fourteen Only
	120.75	Qty Above 125%		910.54	Rupees Nine Hundred Ten And Paise Fifty Four Only

EXECUTIVE ENGINEER-4
KRDCL DEMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
11	525.00	Providing and fixing M.S. Block pipe of 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the existing two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the Engineer-in-charge of work etc., complete including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	m	343.44	Rupees Three Hundred Forty Three And Paise Forty Four Only
12	480.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint etc complete as per specifications and directions of engineer in charge of the work	Sqm	698.54	Rupees Six Hundred Ninety Eight And Paise Fifty Four Only
	45.00	Qty Above 125%		757.90	Rupees Seven Hundred Fifty Seven And Paise Ninety Only
13	8.10	Providing and fixing M.S. Gate as per Chief Architect Drawing, using 50mm x 50mm 14 guage M.S. hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm x 6mm and 16 x 16mm Square rods for verticals alternatively spaced at 4cms c/c in two halves and 40mmx6mm M.S. flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members asshown in the drawing etc., complete. All the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc., complete. The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, with lead and lift, loading and unloading charges, etc complete as per specifications and directions of engineer in charge of the work	Sqm	3110.04	Rupees Three Thousand One Hundred Ten And Paise Four Only
14	60.00	Construction of Embankment with Material Gravel/ Murrum. KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(Including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density) etc complete as per specifications and directions of engineer in charge of the work	cum	320.12	Rupees Three Hundred Twenty And Paise Twelve Only
15	66.00	**Sand Filling** in Foundation Trenches as per Drawing & Technical Specification etc complete as per specifications and directions of engineer in charge of the work	Cum	2922.42	Rupees Two Thousand Nine Hundred Twenty Two And Paise Forty
16	5.00	Providing Granite Benches etc complete as per specifications and directions of engineer in charge of the work	Nos	10000.00	Rupees Ten Thousand Only
		EIRL			

EXECUTIVE ENGINEER-4
KRIDL BEML DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates Quoted by Contractor	
				In Figures	In Words
E1	1.00	Providing, fabricating and fixing special multiplay sustems consists of FRP moulded with aluminium chequered platforms of size 5' x 5' ft with 4 support piller madeour of 75 mm dia G I B Pipes fixed in cement concrete 1:2:4 the flatfomrs are to be covered with tubular slide & mini asuva tunnel slide made up of high quality DRP the slide is to fixed at as height of 11 ft using M S Pipes support at refular intervals of 6ft using M S 25 mm dia pipes with suitable hand rails and steps made out of GFI sheet with tred 4 " with poder coated finishi fine quality ERP with suitable design and as per desing moulded FPR slides are non-corrossive fade free toufh grade durable hard and should prevent UV light the work should be executed as per the standard specifications and direction of the engineer in charge of the work	Set	595000.00	Rupees Five Lakh(s) Ninety Five Thousand Only
E2	1.00	Providing, fabricating and fixing special multiplay sustems consists of flatform with 65 mm dia MS pipe & aluminium chequered plates of size 3 x 3 ft fixed at 5 ft hight from ground level with 4 legs made out of 65 mm dia GI B pipes fixed cement concrre 1:2:4 the flatfomrs are to be covered with tubular slide & mini asuva tunnel slide made up of high quality DRP the slide is to fixed at as height of 11 ft using M S Pipes support at refular intervals of 6ft using M S 25 mm dia pipes with suitable hand rails and steps made out of GFI sheet with tred 4 " with poder coated finishi fine quality ERP with suitable design and as per desing moulded FPR slides are non-corrossive fade free toufh grade durable hard and should prevent UV light the work should be executed as per the standard specifications and direction of the engineer in charge of the work	Set	180000.00	Rupees One Lakh(s) Eighty Thousand Only
E3	1.00	Providing and fixing children play bridge with M.S perforated trnnel wave bridge Arch bridge & hanging bridge made out of MS pipe s and chequered plates uns for a height 11 ft to 5 ft the work should be executed as per the standard specidication and direcction of the engineer in charge odwork with all lead and lift loading and unloading and aby incidental charges required for the successful complete of all works (all swings chains are rubber coated and all 's' hooks are stainless steel) work completion certificate for having made out of GFI sheet with tred 4 " with poder coated finishi fine quality with suitable design and as per desing moulded hard and should prevent UV light the work should be executed as per the standard specifications and direction of the engineer in charge of the work	Set	120000.00	Rupees One Lakh(s) Twenty Thousand Only

I am prepared to execute the above mentioned work written by me in Schedule - B

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor Signature

28/02

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92